BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Construction and improvements of culverts in ward no. 08 Kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	63	KSRRB M 200-12.1. Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable materail with all lifts complete as per specifications (page No. 137, item No. 18.17)	Cum	327.54	Rupees Three Hundred Twenty Seven and Fifty Four Paise Only
2	90.72	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m. (P-258,It.37.48)	Cum	182.32	Rupees One Hundred Eighty Two and Thirty Two Paise Only
3	56.70	KSRB 4-1.3:Providing and layingi n position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.3)	Cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
4	90.72	Reconstruction of size stone masonry with available stones in C.M 1:6 as per direction of the Engineer-in-charge.	Cum	2701.94	Rupees Two Thousand Seven Hundred One and Ninety Four Paise
5	22.68	KSRB 5.2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high, bond stones at two m, apart in each course including cost of materials, labour, curing complete as per specifications. PWD SR 2015-16 (P-23, It5.6)	Cum	4521.96	Rupees Four Thousand Five Hundred Twenty One and Ninety Six Paise Only
6	35.28	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregtes @ 0.878 cum and line aggregates @ 0.459 cum,machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.6)	Cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	315	Providing and fixing 25 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate Approved)	Sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
8	63	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 PWD SR 2013-14 (P-144 & 133, It.No. 17.1)	Cum	106.00	Rupees One Hundred Six Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"